

323-908-1658

FROM : Marquis Const

FAX NO. : +801-253-5005

Apr. 30 2007 03:13PM P1

MARQUIS CONSTRUCTION
 5258 SOUTH 2030 WEST
 TAYLORSVILLE, UTAH 84118
 801-808-0345

PROPOSAL SUBMITTED TO :

April 30, 2007

Attention: John Coursum
 Silver Springs HOA
 c/o Michael Winer
 Park City, Utah

SCOPE:

• pull permit and bond road exc	
• mobilize job site	
• saw cut and remove lid from existing galvanized catch basin in road	<u>Negotiable Costs</u>
• pump out water, compact bottom base, add 6" gravel	\$650.00
• form inside 43" galvanized pipe and tie rebar according to plans	
• pour 4000 psi concrete, sting sides, bottom and lid	
• add ring and grate to lid at asphalt elevation	
• add climbable ladder galvanized or painted steel	
• compact sides and re asphalt to grate	\$400.00
• rotto rooter pressure wash line both ways from clogged area	\$550.00
Total	\$12500.00

Any alteration or deviation from above specifications involving extra costs will be executed only upon written order, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents, or delays beyond our control.


All material is guaranteed to be as specified, and the above work to be performed in a professional manner for the sum of \$12500.00 Respectfully submitted Norman Jessup

If plans or ideas from this proposal are used by others a \$2500 fee will be charged for drawings and ideas.

ACCEPTANCE OF PROPOSAL

The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified.

Signature



Date

5/14/07